

SpaceX is targeting Friday, May 16 for a Falcon 9 launch of 26 Starlink satellites to low-Earth orbit from Space Launch Complex 4 East (SLC-4E) at Vandenberg Space Force Base in California. Liftoff is targeted for 6:43 a.m. PT, with backup opportunities available until 7:00 a.m. PT. If needed, additional launch opportunities are also available on Saturday, May 17 starting at 10:32 a.m. PT.

**@SpaceX**. You can also watch the webcast on the new X TV app. This will be the second flight for the first stage booster supporting this mission, which previously launched one


A live webcast of this mission will begin about five minutes prior to liftoff, which you can watch here and on  ${\bf X}$ 

Starlink mission. Following stage separation, the first stage will land on the Of Course I Still Love You droneship, which will be stationed in the Pacific Ocean. There is the possibility that residents of Santa Barbara, San Luis Obispo, and Ventura counties may hear **one or** 

more sonic booms during the launch, but what residents experience will depend on weather and other conditions.

## **COUNTDOWN**

HR/MIN/SEC	EVENT
00:38:00	SpaceX Launch Director verifies go for propellant load
00:35:00	RP-1 (rocket grade kerosene) loading begins
00:35:00	1st stage LOX (liquid oxygen) loading begins
00:16:00	2nd stage LOX loading begins
00:07:00	Falcon 9 begins engine chill prior to launch
00:01:00	Command flight computer to begin final prelaunch checks
00:01:00	Propellant tank pressurization to flight pressure begins
00:00:45	SpaceX Launch Director verifies go for launch
00:00:03	Engine controller commands engine ignition sequence to start
00:00:00	Falcon 9 liftoff



## All Times Approximate

All Times Approximate	
HR/MIN/SEC	EVENT
00:01:06	Max Q (Moment of peak mechanical stress on the rocket)
00:02:25	1st stage main engine cutoff (MECO)
00:02:28	1st and 2nd stages separate
00:02:35	2nd stage engine starts (SES-1)
00:02:53	Fairing separation
00:06:06	1st stage entry burn begins
00:06:30	1st stage entry burn ends
00:07:50	1st stage landing burn begins
00:08:14	1st stage landing
00:08:39	2nd stage engine cutoff (SECO-1)
00:53:40	2nd stage engine starts (SES-2)
00:53:41	2nd stage engine cutoff (SECO-2)
01:02:33	Starlink satellites deploy